

**Bhagat Phool Singh Mahila Vishwavidyalaya**  
**Department of Engineering Cell**  
**Khanpur Kalan (Sonapat), Haryana-131305**

**Office No. 01263-283007,283530, Fax No. 01263-283779, [www.bpswomenuniversity.ac.in](http://www.bpswomenuniversity.ac.in)**

**NOTICE Re-INVITING TENDER**

Sealed tenders as per schedule/DNIT attached are hereby re-invited on behalf of Registrar in her Office at BPSMV Khanpur Kalan through Registered post/speed post from the Eligible Contractor /L&C Societies/ fabricators/ the firms of similar nature of work. If the date on which the tenders are to be received is declared holiday then the tender will be received on the next working day. The tender shall be opened on the same day in the presence of the tenderer or the authorized representative/agents who may like to be present at that time:-

Sr. No.	Name of Work	App. Cost. In Thousand	Completion Time	Date & Time for Receiving of Tender		Date & Time for opening of Tender	
				Date	Time	Date	Time
1.	Tender for Re-construction of damaged outside stair pillars of Hostel no. 12 ,13 & 14 at BPSMV Khanpur Kalan (Sonapat)	1,64,800/-	15 days	15.04.2021	1:00 pm	15.04.2021	3:00 pm

1. The limited tender/quotation may be sent in favour of Registrar, BPSMV Khanpur Kalan, in sealed envelope through Registered Post/Speed Post with mentioning tender name in bold letter on the envelop.
2. Engineering –In-Charge is competent to increase/decrease the quantity of work.
3. Central/ State taxes will be deducted as applicable from time to time.

**SDE (Civil)**  
**For Registrar**

A copy of the above is forwarded to the following for information and necessary action:-

1. Notice Board.

**SDE (Civil)**

### **DETAILED NOMINCLATURE.**

**NAME OF WORK:-**Tender for Re-construction of damaged outside stair pillars of Hostel no. 12 ,13  
&14 at BPSMV KhanpurKalan (Sonipat)

**Approx. Cost** :Rs. 1,64,800/-

**Date of Tender:** 15.04.2021

Sr. No.	Description of items	Qty.	Unit	Rate to be quoted by the agency in words and in figures, FOR including VAT & taxes.	
				In Figure	In Word
1.	Dismantling Brick Work, Tile Masonry or Tile Lining and Tile Terracing (HSR - 8.5 b) In cement	22.5	Cum		
2.	First class brick work laid in cement sand mortar 1:6 in 1st Storey upto 4 meter above plinth level. (HSR 11.7) i) 1st Floor	4.9	Cum		
ii)	2 <sup>nd</sup> Floor	4.9	Cum		
iii)	3 <sup>rd</sup> Floor	4.9	Cum		
iv)	4 <sup>th</sup> Floor	4.9	Cum		
v)	5 <sup>th</sup> Floor	3.0	Cum		
3.	15 mm thick cement plaster 1:6 on the rough side of single or half brick wall (HSR-15.12)	133.8	Sqm.		
4.	Applying priming coat with cement primer in all shades on newly plastered or concrete exterior surfaces. (HSR-16.25)	133.8	Sqm.		
5.	Providing two coats of exterior acrylic emulsion paint. (HSR-16.79-b). 1st quality	133.8	Sqm.		
6.	Fe-500 EQR TMT steel bar for RCC work, where not included in the complete rate of RCC including bending, binding & placing in the position complete. TATA, TISCON will be preferred. In case of non-availability of RINL, SAIL will be preferred. (HSR 18.22).	5.4	Qtl.		
7.	Cement concrete 1:1.5:3 with stone aggregate 20 mm nominal size for reinforced concrete work in slabs with inclination not exceeding 25 degree with horizontal, excluding steel reinforcement, but	2.0	Cum.		

	including centering and shuttering, laid in position, complete in all respect. (a) 1:1-1/2:3 mix is used, instead of 1:2:4. [HSR. 10.82 + 10.95 (a)].				
8.	Providing and setting of scaffolding as per site requirement of pillars (6 Nos.) heaving 60' height. (NS items)	6	Each		

**JE (Civil)**

**SDE (Civil)**